SHIMOGA DIVISION.

Dated 18th January 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 10th February 1931, till 3 P.M., for constructing the Town Hall at Sagar. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Town Hall at Sagar," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate for the probable cost of Constructing the Town Hall at Sagar.

No.	Items of work	Per	Rate	Terrace roof and Mangalore tiled roof	
				Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork, cutting and levelling the sloping ground.	C.yd.	0 6 0	222	83
2	Earthwork excavating foundation and filling in basement.	„	0 6 0	145	54
3	Filling foundation, stone jelly in mortar.	C.ft.	0 5 6	1,154	397
4	Cut laterite stone in mortar including bond stones, etc.	„	0 8 0	9,948	4,974
5	Cut laterite arch work	„	1 0 0	293	293
6	Teakwood windows with shutters only one side ½ pannelled at bottom and half glazed at top.	S.ft.	2 12 0	334	919
7	Circular pillars 15" dia. 11½' height with base and capitals.	Each	25 0 0	10	250
7A	Circular pillars 9" dia. 10½' height with base and capitals.	„	20 0 0	...	...
8	Teakwood pannelled doors with iron fittings.	S.ft.	2 4 0	290	653
9	Teakwood work wrought and put up including wood oiling complete.	C.ft.	6 0 0	242·34	1,454
10	Iron trusses	Cwt.	15 0 0	40	600
11	Rolled steel joists for verandah bressummer and boxing girders 3" x 4" at 9½ lbs. per R.ft.	„	15 0 0	8·2	123
12	Roofing with 1st Class Mangalore tiles on teak reepers ceiling tiles, etc., complete.	Sqr.	60 0 0	19·00	1,140
13	Roofing with pucca terrace 9" thick ...	„	45 0 0	11·60	522
14	Ornamental ridge tiles set in lime mortar.	R.ft.	1 8 0	26	39
15	Plain ridge tiles set in lime mortar for hips.	„	1 0 0	88	88
16	Plastering with chunnam ...	Sqr.	6 8 0	58·00	377

No.	Items of work	Per	Rate	Terrace roof and Mangalore tiled roof	
				Quantity	Cost
			Rs. a. p.		Rs.
17	White washing 2 coats	Sqr.	0 6 0	58·00	22
18	Pointing with chunnam	,,	3 0 0	33·00	99
19	Flooring with Cuddapah slabs on 3" concrete bed and cement pointing.	,,	40 0 0	4·00	160
20	Flooring with 1st Class Mangalore tiles bed and cement pointing.	,,	40 0 0	16·00	640
21	Chocolate painting (silicate) ...	,,	6 0 0	14·00	84
22	Ornamental parapet wall ...	R.ft.	2 8 0	154	385
23	Do cornice work 9" thick ...	,,	1 4 0	152	190
24	Teakwood eave board 1 foot wide ...	,,	1 0 0	168	168
25	Ornamental work in front of verandah including cornice as per plan	Lumpsum		...	100
26	Vases over parapet walls	Each	10 0 0	5	50
27	Ornamental work over windows as per plan.	,,	15 0 0	15	225
28	Teakwood finials with flags ...	,,	10 0 0	2	20
29	Do pendents over entrance ...	,,	15 0 0	3	45
30	Jungle clearing and forming roads ...	Lumpsum		...	150
31	Unforeseen charges	,,	...	...	100
32	Armoured concrete or stone slabs for steps.	R.ft.	1 0 0	101	101
33	Inscription stone including laying foundation stone, etc., as per separate estimate.	Lumpsum	..	..	200
	Total ...	...	...	...	14,704

N.B.—Quantities noted in the above are approximate and not gauranteed.

K. VENKATARAMAIYA,
Executive Engineer.

MYSORE RAILWAYS, HASSAN.

Abstract Notification dated 19th January 1931.

Attention of the intending contractors is hereby invited to the notice calling for tenders for raising formation over arch bridge No. 32 at mile 14—12-13 on Birur-Shimoga Section, published in page 67, Part VI of the *Mysore Gazette*, dated 15th January 1931.

Tenders will be received any working day up to 2 P.M., on 5th February 1931.

M. RAMAIYA,
Executive Engineer.